

Tool	Waste management requirements and/or desired outcomes		
	Design phase	Construction phase	Operational Phase
Green Star - Office Design v 2 & 3, Office As Built v 2 & 3, Healthcare (Pilot)	A dedicated storage area of adequate size.	Waste Management Plan and contract provisions to re-use and/or recycle from 60% to 80% of construction waste by weight.	Not applicable
Green Star - Office Interiors v 1	Waste management and recycling systems included in the tenancy fitout, whereby either 1 square metre of designated recycling storage space per six work settings with monthly collections or 1 square metre of designated recycling storage space per 24 work settings with weekly collections is provided.	Waste Management Plan implemented and contract provisions to re-use and/or recycle from 40% to 80% of fit-out waste by weight.	Not applicable
Green Star - Retail v 1	Waste storage facilities have been provided	Waste Management Plan and contract provisions to re-use and/or recycle from 60% to 80% of construction waste by weight.	Comprehensive waste and recycling plan for the reduction in the amount, by weight of the retail centre's overall operational waste.
Green Star - Education v 1	A dedicated storage area of adequate size.	Waste Management Plan and contract provisions to re-use and/or recycle from 60% to 90% of construction waste by weight.	Not applicable
Green Star - Office Existing (Extended Pilot)	Not applicable	Not applicable	Demonstrated commitment to waste reduction/recycling monitoring and landfill disposal targets. Dedicated storage area of adequate size. A dedicated storage area of adequate size.
Green Star - Shopping Centre (Pilot)	A dedicated storage area of adequate size.	Waste Management Plan and contract provisions to re-use and/or recycle from 60% to 80% of construction waste by weight.	Waste and Recycling Management Plan for the reduction in the amount, by weight, of the shopping centre's overall operational waste. The Plan must address both the owner and the tenants, and either set explicit annual waste reduction targets or provide a plan to audit the operational waste stream for setting such targets.
Green Star - Industrial (Pilot)	A dedicated storage area of adequate size.	Waste Management Plan and contract provisions to re-use and/or recycle from 60% to 90% of construction waste by weight.	A waste and recycling management plan for the precinct with a shared waste storage facility
NABERS OFFICE waste	Not applicable	Not applicable	Waste generation and diversion performance by recycling systems. Individual behaviours of office workers (distance to centralised waste and recycling bins, etc). Impacts of clusters of office workers (for centralised recycling or waste disposal, localised signage for recycling, etc). Impacts of generic types of office workers on performance (finance, sales, legal, mixed, etc). Composition (grams per person, grams per m2 and % by weight). Contaminant levels in material recovered for recycling. Frequency of collection of waste and recycled materials. Waste avoidance or minimisation approaches (double sided printing, reuse of scrap paper, etc).